BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, BBMP, Bangalore

Tender Notification No.:RRND/EE/Ten/42/2012-13, Date:21.01.2013

Item No.14

Schedule B

Name of Work :Providing RCC drain balance portion of 9th cross, Brindavan Nagara in W No.17

Sl No.	Qty	Description of work	Unit	Rates Quoted by the Contractor M/s Chowdeshwari Constructions	
				In Figures (Rs.)	In Words (Rs.)
1	172.20	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.	cum	123.00	Rupees One Hundred Twenty Three Only
2	172.20	Lead for earthwork and disposal of debris shall be payable at carriage rates by mechanical means including loading and unloading for earthwork (upto 5kms) complete with all lead & lift & as per the direction	cum	73.00	Rupees Seventy Three Only
3	25.83	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregaes @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, cost of all lmaterials labout HOM of machinery curing complete as per specification	cum	3531.00	Rupees Three Thousand Five Hundred Thirty One Only
4	12.60	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	cum	2930.00	Rupees Two Thousand Nine Hundred Thirty Only

Signature of Contractor

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ರಾಜರಾಜೇಶ್ವರಿ ನಗರ ವಿಭಾಗ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Executive Engineer
Rajarajeshwarinagara Division
BBMP

5	21.00	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	65.00	Rupees Sixty Five Only
6	2.52	Providing and laying in position plain cement concrete of mix M15 with OPC cement @ 240 kgs, with 20 mm and down size graded granite metal coarse aggregaes @ 0.878 cum and fine aggregates @ 0.459 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, cost of all lmaterials labout HOM of machinery curing complete as per specification	cum	4008.00	Rupees Four Thousand Eight Only
7	5.80	Providing and laying in position reinforced cement concrete of of design mix with M20 with OPC cement @ 320 kgs with 20mm and down size graded granite metal, coarse aggregates @ 0.878cum and fine aggregtes @ 0.459 cum, with superplastisiser @ 3 lts confirming to IS 9103-1999Reaffirmed-2008, maching mixed,concrete laid in layes not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels retaining walls, return walls, walls (any thickness) including attched plasters columns, piers, abutments, pillars, posts, struts, butteresses, string or lacing courses, parapets, coping, bed block, anchor block, plain window cills, fillets etc. inlduing cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	4762.00	Rupees Four Thousand Seven Hundred Sixty Two Only
8	29.70	Providing & laying cement concrete using 20mm & down size granite coarse aggregages and find aggreagates of ready mixed cement concrete for beams, colums, Staircase and roof with M-20 RCC works laid in 15 cms. thick layers and well compacted including vibrating, curing, etc. including smooth finish in CM 1:3, with all lead and lift etc. complete (exclusive of cost of steel and fabrication & plastering charges.)	cum	5126.00	Rupees Five Thousand One Hundred Twenty Six Only
9	36.08	Providing and fabricating TMT steel reinforcement for RCC work including straightening, cutting bending, hooking, placing in position lapping and /or welding where ever required tying with binding wire anchoring to the adjoining memebers where ever necessary complete as per design(laps, hooks and wastage shall not be measured and paid) cost of all material, labour , HOM of machineries complete as per specifications	Qtl	6657.00	Rupees Six Thousand Six Hundred Fifty Seven Only

Signature of Contractor

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
Executive Engineer
ರಾಜರಾಜೇಶ್ವರಿನಗರ ವಿಭಾಗ
Rajarajeshwarinagara Division
ಬೃಹತ್ ಬೆಂಗಳೂರು
BBMP

10	344.40	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons.	Sqm	222.00	Rupees Two Hundred Twenty Two Only
11	315.00	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 of size 450 x 200 x 400 mm plastering and finishing cutting etc., complete.	Nos	263.00	Rupees Two Hundred Sixty Three Only
12	63.00	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.	Sqm	19.00	Rupees Nineteen Only
13	63.00	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.	Sqm	50.00	Rupees Fifty Only
14	140.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 10 cms thick	Sqm	441.00	Rupees Four Hundred Forty One Only
15	140.00	Providing two line dressing to granite stone slab /granite stone masonry as per specifications.	Sqm	593.00	Rupees Five Hundred Ninety Three Only
16	280.00	Providing chamfering edges to stone slab 2.5 cms. wide as per specifications. (only chamfered length shall be recorded)	Mtr	23.00	Rupees Twenty Three Only

Signature of Contractor

Executive Engineer
Rajarajeshwarinagara Division
BBMP